

Contractor's Bid Sheet
CUMBERLAND STREET IMPROVEMENTS PHASE 1
Village of Lewisburg
Preble County, Ohio

Contractor: _____

Date: _____

Prepared By:
 Kramer & Associates, LLC
 101 North Barron Street
 Eaton, Ohio 45320

ROADWAY

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
	<i>ITEMS FOR UNIT PRICE BID</i>						
204	Subgrade Compaction	1245	S.Y.				
304	Compacted Aggregate Base (Under Curbs)	75	C.Y.				
304	Compacted Aggregate Base (Under Walks & Under Drives)	118	C.Y.				
304	Compacted Aggregate Base (Street)	50	C.Y.				
304	Gravel Drive Repair	2	C.Y.				
407	Tack Coat @ 0.2 gal/S.Y.	53	GAL.				
448	Asphalt Concrete Intermediate Course Type 2, PG 64-22 (Avg. 1 3/4")	13	C.Y.				
448	Asphalt Concrete Surface Course, Type 1, Heavy, PG 70-22, per ODOT Supp. 1055 (Avg. 1 1/4")	9	C.Y.				
448	Asphalt Drive Repair	13	C.Y.				
452	Concrete Drive Repair	6	S.Y.				
452	Driveway Apron (6" Residential)	25	S.Y.				
452	Driveway Apron (8" Commercial)	216	S.Y.				
603	4" Storm Sewer (Downspout Drain)	500	L.F.				
603	12" HDPE Storm Sewer (Labor & Addt'l Mat.No Pipe) Installed in Flowable Backfill	212	L.F.				
603	24" HDPE Storm Sewer (Labor & Addt'l Mat.No Pipe) Installed in Flowable Backfill	216	L.F.				
603	24" HDPE Storm Sewer (Labor & Addt'l Mat.No Pipe) Installed Granular Backfill	623	L.F.				
603	24" HDPE Storm Sewer (Labor & Addt'l Mat.No Pipe) Installed Native Backfill	90	L.F.				
604	Storm Inlet Type 'Y'	10	EACH				

Contractor's Bid Sheet
CUMBERLAND STREET IMPROVEMENTS PHASE 1
Village of Lewisburg
Preble County, Ohio

604	3x3 Catch Basin	1	EACH				
604	Headwall	1	EACH				
608	Concrete Walk (4" Main Line)	4,627	S.F.				
608	Concrete Walk (6" Through Residential Drives)	125	S.F.				
608	Concrete Walk (8" Through Commercial Drives)	955	S.F.				
608	Curb Ramp	7	EACH				
609	Combined Curb & Gutter	1,610	L.F.				
614	Maintenance of Traffic	1	LUMP				
638	8" P.V.C. Waterline, Installed in Flowable Backfill	70	L.F.				
638	8" P.V.C. Waterline Installed in Granular Backfill	15	L.F.				
638	8" 22 1/2 M.J. Bend w/ Restraining Joints	2	EACH				
638	8" Resilient Wedge Valve w/ Box	1	EACH				
638	8" M.J. Cap w/ Restraining Joints	1	EACH				
638	Tie to Existing Waterline	1	LUMP				

TOTAL:

TOTAL WRITTEN IN WORDS:

MBE Supplier

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
	<i>ITEMS FOR UNIT PRICE BID (Pipe Only)</i>						
603	12" HDPE Storm Sewer (Pipe Only)	212	L.F.				
603	24" HDPE Storm Sewer (Pipe Only)	929	L.F.				

TOTAL:

TOTAL WRITTEN IN WORDS: