

**Contractor's Bid Sheet**  
**FRIEND ROAD IMPROVEMENTS PHASE 1A**  
**German Township**  
**Montgomery County, Ohio**

Contractor: \_\_\_\_\_

Date: \_\_\_\_\_

Prepared By:  
 Kramer & Associates, LLC  
 101 North Barron Street  
 Eaton, Ohio 45320

**BASE BID**  
**ROADWAY**

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
	<i>ITEMS FOR UNIT PRICE BID</i>						
202	Mailbox Removed & Re-Set	8	EACH				
203	Borrow (Shoulder Fill)	400	CY				
203	Excavation, Not Including Embankment Construction	343	CY				
204	Subgrade Compaction	1,290	SY				
209	Linear Grading, Typical, As Per Plan	1.22	MILE				
253	Pavement Repair	110	CY				
301	Bituminous Aggregate Base 6" (Widening)	233	CY				
304	Compacted Aggregate Base	110	CY				
407	Tack Coat @ 0.075 gallon/SY	1,128	GAL				
411	Stabilized Crushed Aggregate , As Per Plan	166	CY				
448	Asphalt Concrete Intermediate Course, Type 2, Medium Traffic, PG 64-22 (Wedge)	20	CY				
448	Asphalt Concrete Intermediate Course, Type 1, Medium Traffic, PG 64-22 (Scratch), 1"	206	CY				
448	Asphalt Concrete Intermediate Course, Type 2, Medium Traffic, PG 64-22, 1 1/2"	321	CY				
448	Asphalt Concrete Surface Course, Type 1, Medium Traffic, PG 64-22, 1"	228	CY				
614	Maintaining Traffic	1	LUMP				
642	Center Line, Type 2	0.63	MILE				
642	Edge Line, Type 2	1.26	MILE				
659	Seeding & Mulching	7,000	SY				

**TOTAL:**

**TOTAL WRITTEN IN WORDS:**

**Contractor's Bid Sheet**  
**FRIEND ROAD IMPROVEMENTS PHASE 1A**  
**German Township**  
**Montgomery County, Ohio**

**ADD ALTERNATE  
ROADWAY**

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
	<i>ITEMS FOR UNIT PRICE BID</i>						
202	Pavement Removed	267	SY				
203	Excavation Including Embankment Construction	900	CY				
204	Subgrade Compaction	367	SY				
301	Bituminous Aggregate Base, (Hump Removal)	35	CY				
304	Compacted Aggregate Base, (Hump Removal)	122	CY				
407	Tack Coat @ 0.075 gallon/SY (Under Wedge Areas, See Sheet 6)	34	GAL				

**TOTAL:**

**TOTAL WRITTEN IN WORDS:**