

**Contractor's Bid Sheet**  
**PROJECT RE-BID: CHICKEN BRISTLE ROAD IMPROVEMENTS PHASE 3**  
**JACKSON TOWNSHIP**  
**Montgomery County, Ohio**

Contractor: \_\_\_\_\_

Date: \_\_\_\_\_

Prepared By:  
 Kramer & Associates, LLC  
 101 North Barron Street  
 Eaton, Ohio 45320

**ROADWAY**

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
	<i>ITEMS FOR UNIT PRICE BID</i>						
202	Mailbox Removed & Replaced	12	Each				
203	Excavation Not Including Embankment Construction	150	C.Y.				
203	Borrow (Shoulder Fill)	100	C.Y.				
204	Subgrade Compaction	603	S.Y.				
209	Linear Grading, As Per Plan	1.04	MILE				
253	Pavement Repair	50	C.Y.				
301	Bituminous Aggregate Base (Widening)	100	C.Y.				
304	Compacted Aggregate Base	50	C.Y.				
407	Tack Coat	1,659	GAL				
411	Stabilized Crushed Aggregate, As Per Plan	268	C.Y.				
448	Asphalt Conc. Intermediate Course, Type 2, Medium Traffic, PG 64-22 (Wedge)	71	C.Y.				
448	Asphalt Conc. Intermediate Course, Type 1, Medium Traffic, PG 64-22 (Scratch)	153	C.Y.				
448	Asphalt Conc. Intermediate Course, Type 2, Medium Traffic, PG 64-22	457	C.Y.				
448	Asphalt Conc. Surface Course, Type 1, Medium Traffic, PG 64-22	311	C.Y.				
604	Monument Box Adjusted to Grade	1	EACH				
614	Maintenance of traffic	1	LUMP				
617	Shoulder Preparation, As Per Plan	609	S.Y.				
642	Centerline, Type 2	1.05	MILE				

**TOTAL:**

**TOTAL WRITTEN IN WORDS:**