

Contractor's Bid Sheet
WEST HENDRICKS STREET IMPROVEMENTS
Village of Camden
Preble County, Ohio

Contractor: _____

 Date: _____

Prepared By:
 Kramer & Associates, LLC
 101 North Barron Street
 Eaton, Ohio 45320

ROADWAY

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
	<i>ITEMS FOR UNIT PRICE BID</i>						
203	Excavation including embankment	800	C.Y.				
204	Subgrade Compaction	2,030	S.Y.				
253	Pavement Repair	25	C.Y.				
304	Gravel Drive Repair	3	C.Y.				
304	6" Compacted Aggregate Base (Curbs)	170	C.Y.				
304	4" Compacted Aggregate Base (Drives)	17	C.Y.				
304	10" Compacted Aggregate Base (Street)	300	C.Y.				
407	Tack Coat @ 0.075 Gal/S.Y.	300	GAL				
448	Asphalt Drive Repair	3	C.Y.				
448	Asphalt Concrete Intermediate Course, Type 2, Medium, Pg 64-22, (Wedge)	180	C.Y.				
448	Asphalt Concrete Intermediate Course, Type 1, Medium, Pg 64-22, Scratch (Avg. 1")	110	C.Y.				
448	Asphalt Concrete Intermediate Course, Type 2, Medium, Pg 64-22, (Avg. 1 3/4")	190	C.Y.				
448	Asphalt Concrete Surface Course, Type 1, Medium, Pg 64-22 (Avg. 1 1/4")	135	C.Y.				
452	6" Concrete Drive Repair/Walk	176	S.Y.				
603	Connect to Existing Storm Sewer	7	EACH				
603	12" HDPE Storm Sewer (Labor and Additional Material, No Pipe)	200	L.F.				
603	4" Storm Sewer (Downspout Drain) Type E	500	L.F.				
604	Type "G" Storm Inlet	2	EACH				
604	Type 'Y' Storm Inlet	11	EACH				
604	Reconstruct Existing Inlet	1	EACH				
604	Remove/Plate Existing Inlet	2	EACH				
609	Curb & Gutter	3,050	L.F.				
Spec	Audio/Video Recording of Construction Corridor	1	LUMP				

TOTAL:

TOTAL WRITTEN IN WORDS:

Contractor's Bid Sheet
WEST HENDRICKS STREET IMPROVEMENTS
Village of Camden
Preble County, Ohio

MBE Supplier

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
	<i>ITEMS FOR UNIT PRICE BID (Pipe Only)</i>						
603	12" HDPE Storm Sewer (Pipe Only)	200	L.F.				

TOTAL:

TOTAL WRITTEN IN WORDS:

ADD ALTERNATE 1

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
202	Remove Drive Culverts	2	EACH				
202	Brick Ditch/Curbs/Stone Wall Removed	800	L.F.				
202	Drives/Walks Removed	265	S.Y.				
604	Adjust Manholes to Grade	5	EACH				

TOTAL:

TOTAL WRITTEN IN WORDS: