

**Contractor's Bid Sheet**  
**CUMBERLAND STREET IMPROVEMENTS PHASE 2**  
**Village of Lewisburg**  
**Preble County, Ohio**

Contractor: \_\_\_\_\_

Date: \_\_\_\_\_

Prepared By:  
 Kramer & Associates, LLC  
 101 North Barron Street  
 Eaton, Ohio 45320

**ROADWAY**

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
	<i>ITEMS FOR UNIT PRICE BID</i>						
203	Rock Excavation	150	C.Y.				
204	Subgrade Compaction	1,362	S.Y.				
304	6" Compacted Aggregate Base (Under Curbs)	59	C.Y.				
304	4" Compacted Agg. Base (Walks & Drive Aprons)	85	C.Y.				
304	10" Compacted Aggregate Base (Street)	71	C.Y.				
407	Tack Coat @ 0.075 gal/S.Y.	24	Gal.				
448	Asph. Conc. Intermediate Course, Type 2, PG 64-22	13	C.Y.				
448	Asphalt Conc. Surface Course, Type 1, PG 64-22	9	C.Y.				
448	Asphalt Drive Repair	6	C.Y.				
452	Concrete Drive Repair	14	S.Y.				
452	Concrete Drive Apron (8" Commercial)	103	S.Y.				
603	Connect to Existing Storm Sewer	1	EACH				
603	4" Storm Sewer (Downspout Drain)	500	L.F.				
603	12" HDPE Storm Sewer in Flowable Backfill (Labor and Additional Material, No Pipe)	82	L.F.				
603	15" HDPE Storm Sewer in Flowable Backfill (Labor and Additional Material, No Pipe)	75	L.F.				
603	18" HDPE Storm Sewer in Flowable Backfill (Labor and Additional Material, No Pipe)	68	L.F.				
603	15" Storm Sewer in Granular Backfill (Labor and Additional Material, No Pipe)	219	L.F.				
603	18" Storm Sewer in Granular Backfill (Labor and Additional Material, No Pipe)	241	L.F.				
604	Type 'Y' Inlet	6	EACH				
608	Concrete Walk (4" Main Line)	4,440	S.F.				

**Contractor's Bid Sheet**  
**CUMBERLAND STREET IMPROVEMENTS PHASE 2**  
**Village of Lewisburg**  
**Preble County, Ohio**

608	Concrete Walk (8" Commercial Drives and Alleys)	736	S.F.				
608	Curb Ramp	5	EACH				
609	Combined Curb & Gutter	1,146	L.F.				
614	Maintenance of Traffic	1	LUMP				
638	8" P.V.C. Waterline in Flowable Fill	70	L.F.				
638	8" P.V.C. Waterline in Granular Fill	15	L.F.				
638	8" 22 1/2 M.J. Bend w/Restraining Joints	2	EACH				
638	8" Resilient Wedge Valve w/Box	1	EACH				
638	8" M.J. Cap w/Restraining Joints	1	EACH				
638	Tie to Existing Waterline	1	EACH				
Spec	Audio/Video Recording of Construction Corridor	1	LUMP				

**TOTAL:**

**TOTAL WRITTEN IN WORDS:**

**MBE Supplier**

*ITEMS FOR UNIT PRICE BID (Pipe Only)*

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
603	12" HDPE Storm Sewer (Pipe Only)	82	L.F.				
603	15" HDPE Storm Sewer (Pipe Only)	295	L.F.				
603	18" HDPE Storm Sewer (Pipe Only)	309	L.F.				

**TOTAL:**

**TOTAL WRITTEN IN WORDS:**