

Contractor's Bid Sheet

FRIEND ROAD IMPROVEMENTS PHASE 1B

**German Township
Montgomery County, Ohio**

Contractor: _____

Date: _____

Prepared By:

Kramer & Associates, LLC

101 North Barron Street

Eaton, Ohio 45320

BASE BID

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
<i>ITEMS FOR UNIT PRICE BID</i>							
202	Mailbox Removed & Re-set	8	Each				
203	Borrow (Shoulder Fill)	50	CY				
203	Excavation	804	CY				
204	Subgrade Compaction	1,522	S.Y.				
209	Linear Grading, Typical, As Per Plan	1.12	Miles				
253	Pavement Repair	100	CY				
301	Asphalt Concrete Base 6" (Widening)	254	CY				
304	Aggregate Base (Under Pavement Repairs, if needed)	100	CY				
304	Aggregate Base (Shoulder Widening)	140	CY				
407	Tack Coat @ 0.075 GAL./S.Y.	1,013	Gal.				
411	Stabilized Crushed Aggregate, As Per Plan	36	CY				
448	Asphalt Concrete Intermediate Course, Type 2, Medium Traffic, PG 64-22 (Wedge)	50	CY				
448	Asphalt Concrete Intermediate Course, Type 1, Medium Traffic, PG 64-22 (Scratch), (1")	173	CY				
448	Asphalt Concrete Intermediate Course, Type 2, Medium Traffic, PG 64-22 (1 1/2")	259	CY				
448	Asphalt Concrete Surface Course, Type 1, Medium Traffic, PG 64-22 (1")	195	CY				
604	Monument Box Adjusted to Grade	2	Each				
614	Maintaining Traffic	1	Lump				
642	Center line, Type 2	0.56	Miles				
642	Edge Line, Type 2	1.12	Miles				
659	Seed & Mulch	14,000	SY				

TOTAL:

TOTAL WRITTEN IN WORDS: