

**Contractor's Bid Sheet**  
**SUGAR VALLEY DRIVE IMPROVEMENTS PHASE 1**  
**Village of Camden**  
**Preble County, Ohio**

Contractor: \_\_\_\_\_  
 \_\_\_\_\_  
 Date: \_\_\_\_\_

Date: \_\_\_\_\_

Prepared By:  
 Kramer & Associates, LLC  
 101 North Barron Street  
 Eaton, Ohio 45320

**BASE BID**

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
	<i>ITEMS FOR UNIT PRICE BID</i>						
202	Inlet Removed	1	EACH				
202	Drive Culverts Removed	174	L.F.				
202	Brick/Concrete Curb Removed	1115	L.F.				
202	Remove Concrete Channel	1	EACH				
202	Drive Aprons Removed	114	S.Y.				
202	Remove Existing Headwall	2	EACH				
203	Excavation	200	C.Y.				
203	Excavation (Subbase Failures)	25	C.Y.				
203	Embankment	234	C.Y.				
204	Subgrade Compaction	1188	S.Y.				
207	Temporary Erosion Control	1	LUMP				
253	Pavement Repair	25	C.Y.				
253	Pavement Planing, Asphalt	400	S.Y.				
301	Bituminous Aggregate Base	68	C.Y.				
304	6" Compacted Aggregate Base (Curbs)	102	C.Y.				
304	4" Compacted Aggregate Base (Walks/Drives)	57	C.Y.				
304	6" Compacted Aggregate Base (Subbase Failures)	25	C.Y.				
304	10" Compacted Aggregate Base (Street)	197	C.Y.				
304	12" Compacted Aggregate Base (Shoulder)	4	C.Y.				
304	Gravel Drive Repair	38	S.Y.				
407	Tack Coat @ 0.075 Gal/S.Y.	284	GAL				
448	Asphalt Concrete Intermediate Course, Type 1, Medium Traffic, PG 64-22 (Scratch), (1/2")	53	C.Y.				
448	Asphalt Concrete Intermediate Course, Type 2, Medium Traffic, PG 64-22, (2")	210	C.Y.				

**Contractor's Bid Sheet**  
**SUGAR VALLEY DRIVE IMPROVEMENTS PHASE 1**  
**Village of Camden**  
**Preble County, Ohio**

**BASE BID, CONTINUED FROM PAGE 1**

448	Asphalt Concrete Surface Course, Type 1, Medium Traffic, PG 64-22, (2") as per plan	210	C.Y.				
448	Asphalt Drive Repair	20	S.Y.				
603	4" Storm (Downspout Drain) Type E	50	L.F.				
603	12" Storm Sewer	412	L.F.				
603	15" Storm Sewer	420	L.F.				
603	18" Storm Sewer	81	L.F.				
603	Extend Downspout Drain	1	EACH				
604	Storm Inlet - Type 'Y'	9	EACH				
604	Storm Inlet - Type '2-2B'	2	EACH				
604	Storm Inlet Constructed on Existing Inlet	1	EACH				
604	12" Flared End Section	1	EACH				
604	Set Monument Box	4	EACH				
608	Curb Ramp	2	EACH				
608	6" Concrete Drive Apron (Residential)	116	S.Y.				
608	Concrete Walk 4", 4' Walk (Residential Mainline)	3167	S.F.				
608	Concrete Walk 6" (Residential Drives)	328	S.F.				
608	Concrete Drive Repair	73	S.Y.				
609	Curb & Gutter	1,821	L.F.				
614	Maintenance of Traffic (Labor Only, Materials by Village)	1	LUMP				
642	Centerline, Type 2, (Solid Double Yellow)	0.18	MILE				
653	Topsoil Furnished and Placed	207	C.Y.				
Specia	Audio/Video Recording of Construction Corridor	1	LUMP				

**BASE BID TOTAL:**

**BASE BID TOTAL WRITTEN IN WORDS:**

**Contractor's Bid Sheet**  
**SUGAR VALLEY DRIVE IMPROVEMENTS PHASE 1**  
**Village of Camden**  
**Preble County, Ohio**

**ADDITIONAL ALTERNATE BID NO. 1**

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
<i>ITEMS FOR UNIT PRICE BID</i>							
203	Excavation (Subbase Failures)	40	C.Y.				
253	Pavement Repair	40	C.Y.				
304	6" Compacted Aggregate Base (Subbase Failures)	40	C.Y.				
304	Compacted Aggregate Shoulder (2")	21	C.Y.				
407	Tack Coat @ 0.075 Gal/S.Y.	271	GAL				
448	Asphalt Concrete Surface Course, Type 1, Medium Traffic, PG 64-22, (1.25") as per plan	125	C.Y.				
448	Asphalt Concrete Intermediate Course, Type 2, Medium Traffic, PG 64-22, (1.25")	125	C.Y.				
614	Maintenance of Traffic (Additional Alternate No. 1) (Labor Only, Materials by Village)	1	LUMP				
642	Centerline, Type 2, (Solid Double Yellow)	0.32	MILE				
642	Edge Line, Type 2	0.64	MILE				

**ADDITIONAL ALTERNATE BID NO. 1 TOTAL:**

**ADDITIONAL ALTERNATE BID NO. 1 TOTAL WRITTEN IN WORDS:**

**COMBINED BASE BID AND ADDITIONAL ALTERNATE BID NO. 1 TOTAL:**

**COMBINED BASE BID AND ADDITIONAL ALTERNATE BID NO. 1 TOTAL WRITTEN IN WORDS:**