# Contractor's Bid Sheet ORCHARD STREET IMPROVEMENTS PHASE 1

## Village of West Manchester Preble County, Ohio

Contractor:	 Prepared By:
	 Kramer & Associates, LLC
Date:	101 North Barron Street
	Eaton, Ohio 45320

#### **ROADWAY**

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
	ITEMS FOR UNIT PRICE BID						
203	Excavation	35	C.Y.				
204	Subgrade Compaction	325	S.Y.				
253	Pavement Repair	30	C.Y.				
304	6" Aggregate Base (Curb)	35	C.Y.				
304	6" Aggregate Base (Pavement)	63	C.Y.				
304	4" Aggregate Base (Sidewalk & Aprons)	15	C.Y.				
304	Gravel Alley Repair	2	C.Y.				
407	Tack Coat @ 0.075 gal/S.Y.	95	GAL.				
448	Asphalt Concrete Surface Course, Type 1, Medium, Pg 64-22 (Avg. 1 1/4")	55	C.Y.				
448	Asphalt Concrete Intermediate Course, Type 2, Medium, Pg 64-22, (Avg. 1 3/4")	75	C.Y.				
448	Asphalt Wedging, Type 2, Medium, Pg 64-22	25	C.Y.				
603	4" Storm (Downspout Drain) Type E	100	L.F.				
608	Concrete Drive Apron 8"	30	S.Y.				
608	Concrete Walk (4" Mainline)	730	S.F.				
608	Concrete Curb Ramp	2	EACH				
609	Combined Curb and Gutter	620	L.F.				
Spec	Audio/Video Recording of Construction Corridor	1	LUMP				

TOTAL:		

TOTAL	WRIT	TEN IN	I WOE	-פחק

# Contractor's Bid Sheet ORCHARD STREET IMPROVEMENTS PHASE 1

### Village of West Manchester Preble County, Ohio

#### **ADD ALTERNATE 1**

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
604	Inlet Reconstruction, Type 2-2B	2	EACH				

TOTAL:			

TOTAL	WRITTE	N IN W	ORDS