Contractor's Bid Sheet CAMDEN AVENUE IMPROVEMENTS PHASE 1

Village of West Elkton

Preble County, Ohio

Contractor: _____

Date:

Prepared By: Kramer & Associates, LLC 101 North Barron Street Eaton, Ohio 45320

TIME OF COMPLETION & LIQUIDATED DAMAGES

The Bidder must agree to commence work on or before a date to be specified in a written "Notice to Proceed" of the Board and to fully complete the project as stated below.

This project is partially funded by Preble County's FY10 CDBG program, and partially by an Ohio Public Works Commission Grant. Due to varying requirements for completion in the two different funding programs, the work must be completed as follows:

Storm sewers, concrete work and paving intermediate course, and including all other work not described in the next phase of completion given below – by November 30, 2011. Final surface paving course, topsoil, grading and restoration, seeding and mulching, and pavement marking – by May 15, 2012.

The Contractor is responsible for all detour signage and other detour items for work done after November 30, 2011 (County Engineer's detour signs will not remain in place after November 30, 2011). The Bidder must agree also to pay as liquidated damages, the sum of \$300.00 for each consecutive calendar day thereafter as hereinafter provided in the General Conditions.

Engineer's Estimate for this project: \$239,000.00

BASE BID

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
	ITEMS FOR UNIT PRICE BID						
201	Stumps Removed	1	EACH				
202	Curb Removed	525	LF				
202	Walk Removed	496	SY				
202	Concrete Drives Removed	26	SY				
202	Remove/Replace Wood Fence	1	LUMP				
202	Storm Sewer Removed	50	LF				
203	Rock Excavation	25	CY				
203	Excavation	216	CY				
203	Embankment	201	CY				
203	Subgrade Compaction	983	SY				
253	Pavement Repair	20	CY				
254	Pavement Planing, Asphalt	60	SY				
301	Bituminous Agg. Base	20	CY				
304	Compacted Aggregate (Under Walk & Aprons)	73	CY				
304	Compacted Aggregate (Under Curb & Widening)	102	CY				
304	Compacted Aggregate Base (Subbase Failures)	20	CY				
304	Gravel Drive Repair	7	CY				
407	Tack Coat @ 0.075 gal/SY	140	GAL				
448	Asphalt Scratch Course (1/2" Avg.)	28	CY				
448	Asphalt Wedge Course (2" Avg.)	60	CY				8/30/20

West Elkton - Camden Avenue Improvements Phase 1

8/30/2011

Contractor's Bid Sheet CAMDEN AVENUE IMPROVEMENTS PHASE 1

Village of West Elkton

Preble County, Ohio

	BID - Continued					_	
ITEM	DESCRIPTION	QUANTITY		MATERIALS	LABOR	TOTAL	TOTAL PRICE
448	Asphalt Concrete Intermed. Course	92	CY				
448	Asphalt Concrete Surface Course	79	CY				
448	Asphalt Drive Repair	5	CY				
452	6" Drive Apron	10	SY				
452	8" Drive Apron	84	SY				
452	Concrete Drive Repair	26	SY				
603	12" HDPE Storm Pipe	347	LF				
603	15" HDPE Storm Pipe	50	LF				
603	4" Storm (Downspout Drain) Type E	50	LF				
604	Inlet, Type Y	4	EA				
604	Reconstruct Storm Inlet, as per plan	1	EA				
604	Inlet, 2-2B	1	EA				
608	4' Concrete Walk (4" Mainline)	4,286	SF				
608	4' Concrete Walk (6" Residential Drive)	76	SF				
608	4' Concrete Walk (8" Commercial Drive)	456	SF				
608	Concrete Bridge Walk Slab, as per plan	208	SF				
608	Curb Ramp	3	EA				
609	Curb & Gutter	1,025	LF				
614	Maintenance of Traffic	1	LUMP				
638	Relocate/Adjust Cleanout to Grade	2	EA				
638	Adjust Manhole to Grade	1	EA				
640	Pavement Marking	1	LUMP				
653	Topsoil Furnished and Placed	101	CY				
654	Precast Reinforced Concrete Outlet	2	EA				
659	Seed & Mulch	891	SY				
Spec	Audio/Video Recording of Construction Corridor	1	LUMP				

TOTAL:

TOTAL WRITTEN IN WORDS: