

Contractor's Bid Sheet
AMITY ROAD IMPROVEMENTS PHASE 3
Perry Township
Montgomery County, Ohio

Contractor: _____

 Date: _____

Date: _____

Prepared By:
 Kramer & Associates, LLC
 101 North Barron Street
 Eaton, Ohio 45320

ROADWAY

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
	<i>ITEMS FOR UNIT PRICE BID</i>						
202	Mailbox removed & replaced	6	Each				
203	Borrow (front slope fill)	200	CY				
203	Excavation (Widening)	264	CY				
204	Subgrade Compaction (Widening)	1,212	SY				
209	Linear grading	1.96	Mile				
253	Pavement repair	62	CY				
301	Bituminous aggregate base for widening, 8"	202	CY				
304	Compacted Aggregate Base, (Under Repairs)	62	CY				
304	Compacted Aggregate Base, (Shoulder Widening)	257	CY				
407	Tack coat @ 0.075 gallon/SY	1,639	Gal				
411	Compacted Aggregate Shoulder, Type "A", 8"	65	CY				
448	Asphalt Concrete Intermediate Course, Type 2, (Wedge)	95	CY				
448	Asphalt Concrete Intermediate Course, Type 1, (1/2" Scratch)	149	CY				
448	Asphalt Concrete Intermediate Course, Type 2, 1 1/2"	449	CY				
448	Asphalt Concrete Surface Course, Type 1, 1 1/4"	383	CY				
614	Maintenance of traffic	1	Lump				
642	Edge Line, Type 2	1.96	Mile				
642	Centerline, Type 2	0.98	Mile				

TOTAL:

TOTAL WRITTEN IN WORDS: