

Contractor's Bid Sheet
DODSON ROAD IMPROVEMENTS PHASE 4
Clay Township
Montgomery County, Ohio

Contractor: _____

 Date: _____

Prepared By:
 Kramer & Associates, LLC
 101 North Barron Street
 Eaton, Ohio 45320

ROADWAY

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
	<i>ITEMS FOR UNIT PRICE BID</i>						
202	Mailbox Removed & Replaced	3	Each				
203	Borrow (Shoulder Fill)	300	CY				
203	Excavation Not Including Embankment Construction	421	CY				
204	Subgrade Compaction	1,830	SY				
209	Linear Grading, Typical As Per Plan	2.13	Mile				
253	Pavement Repair	115	CY				
301	Bituminous Aggregate Base (Widening)	306	CY				
304	Compacted Aggregate Base (Under Pavement Repairs)	115	CY				
407	Tack Coat	1,701	Gal				
411	Stabilized Crushed Aggregate, As Per Plan	275	CY				
448	Asphalt Concrete Intermediate Course, Type 2, Medium Traffic, PG 64-22 (Wedge)	20	CY				
448	Asphalt Concrete Intermediate Course, Type 1, Medium Traffic, PG 64-22 (Scratch)	157	CY				
448	Asphalt Concrete Intermediate Course, Type 2, Medium Traffic, PG 64-22	473	CY				
448	Asphalt Concrete Surface Course, Type 1, Medium Traffic, PG 64-22	319	CY				
614	Maintenance of Traffic	1	Lump				
642	Centerline, Type 2	1.06	Mile				
642	Edge Line, Type 2	2.12	Mile				

TOTAL:

TOTAL WRITTEN IN WORDS: