Contractor's Bid Sheet CUMBERLAND STREET IMPROVEMENTS PHASE 3

Village of Lewisburg Preble County, Ohio

Kramer & Associates, LL
101 North Barron Street
Eaton, Ohio 45320

Prepared By:

Contractor:	Date:	

ROADWAY

ITEM DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
ITEMS FOR UNIT PRICE BID						
203 Excavation, Including Embankment	750	C.Y.				
203 Excavation, Not Incl. Embkmt. (Subbase Failures)	20	C.Y.				
203 Borrow, as per plan (used as Embankment)	100	C.Y.				
203 Rock Excavation	50	C.Y.				
204 Subgrade Compaction	2,495	S.Y.				
253 Pavement Repair	20	C.Y.				
254 Pavement Planing, Asphalt	500	S.Y.				
301 Bituminous Aggregate Base	132	C.Y.				
304 4" Compacted Aggregate Base (Walks & Drives)	110	C.Y.				
304 6" Compacted Aggregate Base (Curbs)	95	C.Y.				
304 Compacted Aggregate Base (Street)	263	C.Y.				
304 Compacted Aggregate Base (Subbase Failures)	20	C.Y.				
304 Gravel Drive Repair, as per plan	52	C.Y.				
407 Tack Coat @ 0.075 gal./S.Y.	71	GAL.				
448 Asphalt Wedge, as per plan, Type 1 PG 64-22	50	C.Y.				
448 Asphalt Drive Repair, as per plan, Type 1 PG 64-22	6	C.Y.				
448 3" Asphalt Conc. Surface Course, Type 1 PG 64-22	80	C.Y.				
452 Concrete Drive Repair, as per plan	143	S.Y.				
452 Concrete Drive Apron 6" (Residential), as per plan	166	S.Y.				
603 4" Storm (Downspout Drain) Type E	200	L.F.				
603 6" Storm Sewer HDPE, as per plan, in Lawn (Labor and Additional Material, No Pipe)	45	L.F.				
603 12" Storm Sewer HDPE, as per plan, in Street (Labor and Additional Material, No Pipe)	37	L.F.				
603 12" Storm Sewer RCP CL-IV, as per plan, in Street (Labor and Additional Material, No Pipe)	10	L.F.				

Lewisburg - Cumberland Street Improvements Phase 3 28-07-03-2008-071

5/18/2011

Contractor's Bid Sheet CUMBERLAND STREET IMPROVEMENTS PHASE 3

Village of Lewisburg Preble County, Ohio

Prepared By:

Kramer & Associates, LLC 101 North Barron Street Eaton, Ohio 45320

ROADWAY (CONTINUED FROM PAGE 1)

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
603	12" Storm Sewer RCP CL-IV, as per plan, in Lawn (Labor and Additional Material, No Pipe)	200	L.F.				
604	Type 'D' Storm Inlet, as per plan	5	EACH				
604	Type 'Y' Storm Inlet, as per plan	1	EACH				
604	Reconstruct Storm Inlet, as per plan	4	EACH				
604	Reconstruct/Adjust Manhole to Grade	3	EACH				
608	Curb Ramp	5	EACH				
608	Concrete Walk 4", 5' Walk (Residential Mainline)	6,751	S.F.				
608	Concrete Walk 6", 5' Walk (Residential Drives)	605	S.F.				
609	Curb & Gutter, as per plan	1,706	L.F.				
614	Maintenance of Traffic	1	LUMP				
Spec	Audio/Video Recording of Construction Corridor	1	LUMP				

т	O	т	Λ		
	v	ш.	м	ᆫ	•

TOTAL WRITTEN IN WORDS:

MBE SUPPLIER

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
	ITEMS FOR UNIT PRICE BID (Pipe Only)						
603	6" Storm Sewer HDPE (Pipe Only)	45	L.F.				
603	12" Storm Sewer HDPE (Pipe Only)	37	L.F.				
603	12" Storm Sewer RCP CL-IV (Pipe Only)	210	L.F.				

TOTAL:		

TOTAL WRITTEN IN WORDS: