

Contractor's Bid Sheet
FIRE HYDRANT REPLACEMENT PHASE 1

Village of West Manchester
 Preble County, Ohio

Contractor: _____

Date: _____

Prepared By:
 Kramer & Associates, LLC
 101 North Barron Street
 Eaton, Ohio 45320

At the time this contract is to be awarded, the Owner will consider the lowest and most responsive bids for the Base Bid, Additional Alternate No. 1 Bid, Additional Alternate No. 2 Bid, and the Combined Totals of the Base Bid plus the Additional Alternate Bids. If the Base Bid exceeds the amount of funds then estimated by the Owner as available to finance the project, the Owner may reject all bids. If funding limitations require, the contract may be awarded on only the lowest and most responsive bid for the Base Bid. If funding allows, the contract may be awarded on the lowest and most responsive bid for the Combined Totals of the Base Bid and of one or both of the Additional Alternate Bids.

Engineer's Estimate for this project:

Base Bid	\$37,500.00
Addn'l. Alt. No. 1	\$ 7,050.00
Addn'l. Alt. No. 2	\$ 1,800.00

BASE BID

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
	<i>ITEMS FOR UNIT PRICE BID</i>						
202	Remove Fire Hydrant	6	EACH				
614	Maintenance of Traffic	1	LUMP				
638	6"x6" M.J. Tee w/Mechanical Restraints	1	EACH				
638	4"x6" M.J. Reducer w/Mechanical Restraints	2	EACH				
638	6" M.J. 45 Bend w/Mechanical Restraints	3	EACH				
638	6" M.J. 90 Bend w/Mechanical Restraints	1	EACH				
638	4" M.J. Cutting-In Sleeve w/Mechanical Restraints	1	EACH				
638	6"x6" M.J. Tapping Sleeve and Valve w/Box w/Mechanical Restraints	1	EACH				
638	6" M.J. Resilient Wedge Valve w/Box	5	EACH				
638	6" PVC Waterline w/Granular Backfill	100	L.F.				
638	Fire Hydrant w/Restraint and Blocking	6	EACH				
Spec.	Audio/Video Recording of Construction Corridor	1	LUMP				

TOTAL:

TOTAL WRITTEN IN WORDS:

Contractor's Bid Sheet
FIRE HYDRANT REPLACEMENT PHASE 1
Village of West Manchester
Preble County, Ohio

ADDITIONAL ALTERNATE NO. 1

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
	<i>ITEMS FOR UNIT PRICE BID</i>						
202	Remove Fire Hydrant (N.W. Cor. of Scott St. and High St.)	1	EACH				
202	Remove Fire Hydrant (N.E. Cor. of Race St. and Walnut St.)	1	EACH				
638	4" M.J. Cutting-In Sleeve w/Mechanical Restraints	1	EACH				
638	4"x6" M.J. Reducer w/Mechanical Restraints	2	EACH				
638	6" M.J. 45 Bend w/Mechanical Restraints	1	EACH				
638	6"x6" M.J. Tee w/Mechanical Restraints	1	EACH				
638	6" M.J. Resilient Wedge Valve w/Box	1	EACH				
638	6" PVC Waterline w/Granular Backfill	15	L.F.				
638	Fire Hydrant w/Restraint and Blocking	1	EACH				

ADD ALT. NO. 1 TOTAL:

ADD ALT. NO. 1 TOTAL WRITTEN IN WORDS:

ADDITIONAL ALTERNATE NO. 2

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
	<i>ITEMS FOR UNIT PRICE BID</i>						
202	Remove Water Valve (at Water Treatment Plant, East Valve)	1	EACH				
638	6" M.J. Resilient Wedge Valve w/Box	1	EACH				
638	4" M.J. Cutting-In Sleeve w/Mechanical Restraints	1	EACH				

ADD ALT. NO. 2 TOTAL:

ADD ALT. NO. 2 TOTAL WRITTEN IN WORDS: