

Contractor's Bid Sheet
EAST STREET NEIGHBORHOOD IMPROVEMENTS RE-BID
Village of Gratis
Preble County, Ohio

Contractor: _____

Date: _____

Prepared By:
Kramer & Associates, LLC
101 North Barron Street
Eaton, Ohio 45320

| ITEM | DESCRIPTION | QUANTITY | UNIT | MATERIALS | LABOR | TOTAL | TOTAL PRICE |
|------|---|----------|------|-----------|-------|-------|-------------|
| | ITEMS FOR UNIT PRICE BID | | | | | | |
| 201 | Tree and/or Stump Removal | 8 | EA | | | | |
| 202 | Curb Removal | 1150 | LF | | | | |
| 202 | Pavement Removal (Not Including Pavement Repair or Trenching) | 332 | SY | | | | |
| 202 | Concrete Removal (Walks) | 680 | SY | | | | |
| 202 | Inlet Removed | 2 | EA | | | | |
| 202 | Storm Sewer Removed | 60 | LF | | | | |
| 203 | Excavation, Not Including Embankment | 232 | CY | | | | |
| 203 | Excavation, Not Including Embankment (Subbase Failures) | 20 | CY | | | | |
| 203 | Embankment | 185 | CY | | | | |
| 204 | Subgrade Compaction | 1250 | SY | | | | |
| 207 | Temporary Erosion Control | 1 | LUMP | | | | |
| 253 | Pavement Repair | 10 | CY | | | | |
| 254 | Pavement Planing, Asphalt | 200 | SY | | | | |
| 301 | Asphalt Wedge | 160 | CY | | | | |
| 304 | Compacted Aggregate Base 6" (Curbs) | 85 | CY | | | | |
| 304 | Compacted Aggregate Base 4" (Walks/Aprons) | 85 | CY | | | | |
| 304 | Compacted Aggregate Base 6" (Subbase Failures) | 10 | CY | | | | |
| 304 | Gravel Drive Repair | 20 | CY | | | | |
| 407 | Tack Coat @ 0.20 gal/S.Y. | 265 | GAL | | | | |
| 448 | Asphalt Drive Repair | 10 | CY | | | | |
| 448 | Asphalt Surface/Intermediate Course, Type 1, PG 64-22 | 125 | CY | | | | |
| 452 | Concrete Drive Apron 6" (Residential) | 15 | SY | | | | |
| 452 | Concrete Drive Apron 8" (Commercial) | 15 | SY | | | | |
| 452 | Concrete Walk 4", 5' Walk (Residential Mainline) | 6275 | SF | | | | |
| 452 | Concrete Walk 8" (Commercial Drives) | 130 | SF | | | | |
| 603 | 4" Storm (Downspout Drain) Type E | 100 | LF | | | | |
| 603 | 12" Storm Sewer | 350 | LF | | | | |

Contractor's Bid Sheet
EAST STREET NEIGHBORHOOD IMPROVEMENTS RE-BID

Village of Gratis
 Preble County, Ohio

| | | | | | | | |
|---------|--|------|------|--|--|--|--|
| 604 | Adjust Manhole to Grade | 1 | EA | | | | |
| 604 | Storm Inlet - 2-2B | 4 | EA | | | | |
| 604 | Storm Inlet - Type 'Y' | 3 | EA | | | | |
| 604 | Adjust Storm Inlet to Grade | 5 | EA | | | | |
| 604 | Reconstruct Storm Inlet | 1 | EA | | | | |
| 608 | Curb Ramp | 8 | EA | | | | |
| 608 | Concrete Step | 10 | LF | | | | |
| 609 | Curb & Gutter | 1490 | LF | | | | |
| 614 | Maintain Traffic | 1 | LUMP | | | | |
| 642 | Removal of Pavement Marking | 1 | LUMP | | | | |
| 642 | Pavement Marking | 1 | LUMP | | | | |
| 638 | Connect to Existing Waterline | 3 | EA | | | | |
| 638 | 6" Cut-in-Sleeve | 1 | EA | | | | |
| 638 | 4" Cut-in-Sleeve | 1 | EA | | | | |
| 638 | 8" Waterline | 705 | LF | | | | |
| 638 | 8"X8" M.J. Tee w/ Mechanical Restraints | 1 | EA | | | | |
| 638 | 4"X4" M.J. Tee w/ Mechanical Restraints | 1 | EA | | | | |
| 638 | 8"X4" Reducer w/ Mechanical Restraints | 1 | EA | | | | |
| 638 | 8"X6" Reducer w/ Mechanical Restraints | 1 | EA | | | | |
| 638 | 8"X6" M.J. Tee w/ Mechanical Restraints | 2 | EA | | | | |
| 638 | 6"X6" M.J. Tee w/ Mechanical Restraints | 1 | EA | | | | |
| 638 | 8" M.J. 45° Bend w/ Mechanical Restraints | 2 | EA | | | | |
| 638 | 8" M.J. Resilient Wedge Valve w/ Box | 3 | EA | | | | |
| 638 | 6" PVC Waterline (Fire Hydrants) | 20 | LF | | | | |
| 638 | 6" M.J. Resilient Wedge Valve w/ Box | 2 | EA | | | | |
| 638 | 3/4" Corporation Stop | 14 | EA | | | | |
| 638 | 8" X 3/4" Saddle | 14 | EA | | | | |
| 638 | 3/4" PE DR9 CTS Water Service, In Trench, Short (East) | 150 | LF | | | | |
| 638 | 3/4" PE DR9 CTS Water Service, Directional Bore, Long (West) | 280 | LF | | | | |
| 638 | Fire Hydrant w/ Restraint and Blocking | 2 | EA | | | | |
| 638 | Meter Pit Remove and Reset | 3 | EA | | | | |
| 638 | Adjust Valves/Meters to Grade | 4 | EA | | | | |
| 638 | Curb Stop with Box | 6 | EA | | | | |
| Special | Audio/Video Recording of Construction Corridor | 1 | LUMP | | | | |

TOTAL:

TOTAL WRITTEN IN WORDS: