

Contractor's Bid Sheet
EAST STREET NEIGHBORHOOD IMPROVEMENTS

Village of Gratis
 Preble County, Ohio

Revised per Addendum #1 August 25, 2010

Contractor: _____

Date: _____

Prepared By:

Kramer & Associates, LLC

101 North Barron Street

Eaton, Ohio 45320

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
	<i>ITEMS FOR UNIT PRICE BID</i>						
201	Tree and/or Stump Removal	8	EA				
202	Curb Removal	1150	LF				
202	Pavement Removal (Not Including Pavement Repair or Trenching)	332	SY				
202	Concrete Removal (Walks)	680	SY				
202	Inlet Removed	2	EA				
202	Storm Sewer Removed	60	LF				
203	Excavation, Not Including Embankment	232	CY				
203	Excavation, Not Including Embankment (Subbase Failures)	20	CY				
203	Embankment	185	CY				
204	Subgrade Compaction	1250	SY				
207	Temporary Erosion Control	1	LUMP				
253	Pavement Repair	10	CY				
254	Pavement Planing, Asphalt	200	SY				
301	Asphalt Wedge	160	CY				
304	Compacted Aggregate Base 6" (Curbs)	85	CY				
304	Compacted Aggregate Base 4" (Walks/Aprons)	85	CY				
304	Compacted Aggregate Base 6" (Subbase Failures)	10	CY				
304	Gravel Drive Repair	20	CY				
407	Tack Coat @ 0.20 gal/S.Y.	265	GAL				
448	Asphalt Drive Repair	10	CY				
448	Asphalt Surface/Intermediate Course, Type 1, PG 64-22	125	CY				
452	Concrete Drive Apron 6" (Residential)	15	SY				
452	Concrete Drive Apron 8" (Commercial)	15	SY				
452	Concrete Walk 4", 5' Walk (Residential Mainline)	6275	SF				
452	Concrete Walk 8" (Commercial Drives)	130	SF				
603	4" Storm (Downspout Drain) Type E	100	LF				
603	12" Storm Sewer	350	LF				
603	Connect to Existing Waterline	3	EA				

Contractor's Bid Sheet
EAST STREET NEIGHBORHOOD IMPROVEMENTS

Village of Gratis
 Preble County, Ohio

Revised per Addendum #1 August 25, 2010

604	Adjust Manhole to Grade	1	EA				
604	Storm Inlet - 2-2B	4	EA				
604	Storm Inlet - Type 'Y'	3	EA				
604	Adjust Storm Inlet to Grade	5	EA				
604	Reconstruct Storm Inlet	1	EA				
608	Curb Ramp	8	EA				
608	Concrete Step	10	L.F.				
609	Curb & Gutter	1490	LF				
614	Maintain Traffic	1	LUMP				
642	Removal of Pavement Marking	1	LS				
642	Pavement Marking	1	LUMP				
638	Connect to Existing Waterline	3	EA				
638	6" Cut-in-Sleeve	1	EA				
638	4" Cut-in-Sleeve	1	EA				
638	8" Waterline	705	LF				
638	8"X8" M.J. Tee w/ Mechanical Restraints	1	EA				
638	4"X4" M.J. Tee w/ Mechanical Restraints	1	EA				
638	8"X4" Reducer w/ Mechanical Restraints	1	EA				
638	8"X6" Reducer w/ Mechanical Restraints	3	EA				
638	6"X6" M.J. Tee w/ Mechanical Restraints	1	EA				
638	8" M.J. 45° Bend w/ Mechanical Restraints	1	EA				
638	8" M.J. Resilient Wedge Valve w/ Box	3	EA				
638	6" PVC Waterline (Fire Hydrants)	20	LF				
638	6" M.J. Resilient Wedge Valve w/ Box	2	EA				
638	Corporation Stop w/ Reducer	9	EA				
638	8"X1" Saddle	9	EA				
638	3/4" PE DR9 CTS Water Service, In Trench, Short (East)	150	LF				
638	3/4" PE DR9 CTS Water Service, Directional Bore, Long (West)	105	LF				
638	Fire Hydrant w/ Restraint and Blocking	2	EA				
638	Meter Pit Remove and Reset	2	EA				
638	Adjust Valves/Meters to Grade	6	EA				
638	Curb Stop with Box	5	EA				
Special	Audio/Video Recording of Construction Corridor	1	LUMP				

TOTAL:

TOTAL WRITTEN IN WORDS: