

Contractor's Bid Sheet
AMITY ROAD IMPROVEMENTS PHASE 4
Perry Township
Montgomery County, Ohio

Contractor: _____

Date: _____

Prepared By:
 Kramer & Associates, LLC
 101 North Barron Street
 Eaton, Ohio 45320

Date: _____

ROADWAY

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
	<i>ITEMS FOR UNIT PRICE BID</i>						
202	Mailbox Removed & Replaced	8	Each				
203	Borrow (Shoulder Fill)	200	CY				
203	Excavation, Not Including Embankment Construction	413	CY				
204	Subgrade Compaction	2,109	SY				
209	Linear Grading, Typical, As Per Plan	1.98	Mile				
253	Pavement Repair	60	CY				
301	Asphalt Concrete Base, PG 64-22 (Widening)	353	CY				
304	Compacted Aggregate Base, (Under Pavement Repairs)	60	CY				
304	Compacted Aggregate Base, (Shoulder Widening)	257	CY				
407	Tack Coat	1,689	Gal				
411	Stabilized Crushed Aggregate, As Per Plan	60	CY				
448	Asphalt Concrete Intermediate Course, Type 2, Medium Traffic, PG 64-22, (Wedge)	50	CY				
448	Asphalt Concrete Intermediate Course, Type 1, Medium Traffic, PG 64-22 (Scratch)	154	CY				
448	Asphalt Concrete Intermediate Course, Type 2, Medium Traffic, PG 64-22	465	CY				
448	Asphalt Concrete Surface Course, Type 1, Medium Traffic, PG 64-22, As Per Plan	396	CY				
614	Maintaining Traffic	1	Lump				
642	Centerline, Type 2	1.00	Mile				
642	Edge Line, Type 2	2.00	Mile				

TOTAL:

TOTAL WRITTEN IN WORDS: