

Contractor's Bid Sheet

Village of Camden

Water System Interconnection to Southwest Regional Water District

Preble County, Ohio

Contractor: _____
 Address: _____
 Phone/Fax: _____
 E-mail: _____

Date: _____

Form prepared By: Kramer & Associates, LLC
 101 North Barron Street
 Eaton, Ohio 45320
 P. (937) 456-1332 / F. (937) 456-6912

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
<i>ITEMS FOR UNIT PRICE BID</i>							
Part 1 (Camden-West Elkton Road/Free Short Pike)							
201	Clearing, Grubbing, Removal	1	Lump				
202	Sign Removal and Replaced, As Per Plan	10	Each				
203	Rock Excavation	150	C.Y.				
207	Temporary Seeding	1	Lump				
614	Maintaining Traffic, As Per Plan	1	Lump				
638	6" AWWA C900 PVC Waterline, Open Trench (In Native Backfill Area)	559	L.F.				
638	6" AWWA C900 PVC Waterline, Open Trench (In Granular Backfill Area)	24	L.F.				
638	6" SDR21 PVC Waterline, Open Trench (In Native Backfill Area)	5,940	L.F.				
638	6" SDR21 PVC Waterline, Open Trench (In Granular Backfill Area)	1,598	L.F.				
638	6" SDR21 PVC Waterline, Open Trench (In Low Strength Mortar Backfill Area)	80	L.F.				
638	8" AWWA C900 PVC Waterline, Open Trench (In Native Backfill Area)	508	L.F.				
638	8" AWWA C900 PVC Waterline, Open Trench (In Granular Backfill Area)	248	L.F.				
638	Directional Bore, 10" HDPE Carrier Pipe in 16" HDPE Casing	140	L.F.				
638	Directional Bore, 6" HDPE (No Casing)	118	L.F.				
638	Directional Bore, 6" HDPE Carrier Pipe in 10" HDPE Casing	46	L.F.				
638	8" M.J. Resilient Wedge Valve w/PIV	1	L.F.				
638	8" M.J. Resilient Wedge Valve w/Box	2	Each				
638	6" M.J. Resilient Wedge Valve w/Box	14	Each				
638	10"x8" M.J. Reducer	2	Each				
638	8"x6" M.J. Reducer	3	Each				
638	8"x8" M.J. Tee with Mechanical Restraints	2	Each				
638	8"x6" M.J. Tee with Mechanical Restraints	2	Each				
638	6"x6" M.J. Tee with Mechanical Restraints	6	Each				
638	6" M.J. 22 1/2° El, with Mechanical Restraints	1	Each				
638	6" M.J. 45° El, with Mechanical Restraints	14	Each				
638	8" M.J. 45° El, with Mechanical Restraints	1	Each				
638	6" M.J. 90° El, with Mechanical Restraints	1	Each				
638	6" M.J. Tapping Valve	2	Each				
638	6" Cutting-In Sleeve	1	Each				

Contractor's Bid Sheet

Village of Camden

Water System Interconnection to Southwest Regional Water District

Preble County, Ohio

638	Fire Hydrant, As Per Plan	5	Each				
638	Connect to Existing Waterline	2	Each				
659	Seeding and Mulching, Class 1 Lawn Mix	1,852	S.Y.				
659	Seeding and Mulching, Class 2 Roadside Mix	16,660	S.Y.				
659	Fertilizer	1	Lump				
Spec	Metering Station Complete, Incl. Building, Controls, and Sitework	1	Lump				
Spec	Water Main Repairs, Existing System (ALLOWANCE)	1	Lump	-	-	6,000.00	6,000.00
Spec	DP&L Service (ALLOWANCE)	1	Lump	-	-	10,000.00	10,000.00
Spec	Audio/Video Recording of Construction Corridor - Part 1	1	Lump				
Part 2 (Wayne Trace Road/Northern Road)							
201	Clearing, Grubbing, Removal	1	Lump				
202	Sign Removal and Replaced, As Per Plan	5	Each				
202	Remove Existing Concrete Tile	185	L.F.				
202	Remove and Replace Existing Drive Culvert, 12" or 15"	24	L.F.				
203	Rock Excavation	150	C.Y.				
207	Temporary Seeding	1	Lump				
603	12" H.D.P.E. Storm (Ditch Culvert)	185	L.F.				
614	Maintaining Traffic, As Per Plan	1	Lump				
638	6" SDR21 PVC Waterline, Open Trench (In Native Backfill Area)	6,649	L.F.				
638	6" SDR21 PVC Waterline, Open Trench (In Granular Backfill Area)	55	L.F.				
638	Directional Bore, 6" HDPE Carrier Pipe in 10" HDPE Casing	46	L.F.				
638	6" M.J. Resilient Wedge Valve w/Box	9	Each				
638	6" Waterline Plug	1	Each				
638	6"x6" M.J. Tee with Mechanical Restraints	4	Each				
638	6" M.J. 22 1/2° El, with Mechanical Restraints	1	Each				
638	6" M.J. 45° El, with Mechanical Restraints	14	Each				
638	6" Cutting-In Sleeve	1	Each				
638	Fire Hydrant, As Per Plan	2	Each				
638	Connect to Existing Waterline	2	Each				
659	Seeding and Mulching, Class 1 Lawn Mix	1,474	S.Y.				
659	Seeding and Mulching, Class 2 Roadside Mix	13,260	S.Y.				
659	Fertilizer	1	Lump				
Spec	Audio/Video Recording of Construction Corridor - Part 2	1	Lump				

TOTAL:

TOTAL WRITTEN IN WORDS: