

**Contractor's Bid Sheet**  
**DILLMAN ROAD (T-209) RECONSTRUCTION**  
**Somers Township**

Contractor: \_\_\_\_\_  
 Address: \_\_\_\_\_  
 \_\_\_\_\_  
 Contact: \_\_\_\_\_

Date: \_\_\_\_\_  
 Phone: \_\_\_\_\_  
 Fax: \_\_\_\_\_  
 E-mail: \_\_\_\_\_

**Prepared By:**  
**Kramer & Associates, LLC**  
**101 North Barron Street**  
**Eaton, Ohio 45320**

*(Bidder's failure to complete this form in its entirety may cause the Bidder's proposal to be rejected as being non-responsive. Please complete all contact information above and spaces provided below.)*

**Engineer's Estimate for Base Bid: \$400,000.00**

**BASE BID**

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
	<i>ITEMS FOR UNIT PRICE BID</i>						
202	Guardrail Removed	333	LF				
202	Existing Headwall Removed, Sta. 16+20	2	Each				
202	Existing Roadway Culvert Removed	83	LF				
203	Borrow (shoulder fill)	600	CY				
203	Excavation Not Including Embankment Construction	589	CY				
203	Rock Excavation	10	CY				
204	Subgrade Compaction	3,209	SY				
209	Linear grading, Typical, as per plan	3.02	Mile				
253	Pavement repair	50	CY				
301	Bituminous aggregate base (Widening)	539	CY				
304	Compacted Aggregate Base, (Under Pavement Repairs)	50	CY				
304	Compacted Aggregate Base, (Shoulder Widening)	395	CY				
407	Tack Coat	2,474	Gal				
411	Stabilized Crushed Aggregate, As per Plan	99	CY				
448	Asphalt Concrete Intermediate Course, Type 2, Medium Traffic, PG 64-22 (Wedge)	50	CY				
448	Asphalt Concrete Intermediate Course, Type 1, Medium Traffic, PG 64-22	452	CY				
448	Asphalt Concrete Surface Course, Type 1, Medium Traffic, PG 64-22	465	CY				
603	Roadway Culvert, Type "A" Reinforced Concrete Pipe (24" & Under)	104	LF				

**BASE BID - Continued**

603	Roadway Culvert, Type "B" 60" HDPE Smooth Lined (ADS N-12 or Equal)	60	LF				
603	Plastic Pipe, 6" (To be used as directed by the Engineer, If needed)	100	LF				
604	Concrete Headwall, as per plan (See detail on Sheet 8)	2	Each				
606	Guardrail, Type 5	1,382	LF				
614	Maintaining Traffic (Labor Only, Materials by Township)	1	Lump				
624	Mobilization	1	Lump				
642	Center Line, Type 2	1.51	Mile				
642	Edge Line, Type 2	3.02	Mile				
Special	Flowline Work, as per plan, Sta. 11+80	1	Lump				
Special	Flowline Work, as per plan, Sta. 14+30	1	Lump				

BASE BID TOTAL:

BASE BID TOTAL WRITTEN IN WORDS:

**Engineer's Estimate for Additional Alternate Bid: \$20,000.00**

**ADDITIONAL ALTERNATE BID**

*(If additional alternate items below are not chosen, these items will be performed by the Township, as listed on the General Summary plan sheet, page 6 of 13)*

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
<i>ITEMS FOR UNIT PRICE BID</i>							
659	Seeding & mulching	17,725	SY				
659	Commercial Fertilizer	1.80	Ton				

ADDITIONAL ALTERNATE BID TOTAL:

ADDITIONAL ALTERNATE BID TOTAL WRITTEN IN WORDS:

COMBINED BASE BID AND ADDITIONAL ALTERNATE BID TOTAL:

COMBINED BASE BID AND ADDITIONAL ALTERNATE BID TOTAL WRITTEN IN WORDS: